

EXHIBIT A SCOPE OF WORK

Task 1: Perform brush clearing along 2.9 miles of Pleasant Valley Rd, from Highway 20 to Wildflower drive and along 3.18 miles of Washington Rd from MP3 to Maybert Rd. Brush clearing shall follow the same provisions outlined in Section 17 of Division III: Earthwork and Landscape in the bid documents for the Egress/Ingress Fire Safety Project, and County Change Order #1 for Scotch Broom Treatment.

Task 2: Remove remaining storm debris from the December 27, 2021, Winter Storm along 97 miles of County maintained roadways. Removal of this material will include the following:

1. Removal of all storm debris including fallen trees of all sizes, broken limbs, and small branches larger than 1 inch in diameter and 1 foot in length, and litter under 20 pounds (only in areas with storm debris damage) on both sides of the road that rests within 15 feet from the road edge.
2. Any downed trees that extend past 15 feet from the road edge shall be cut at the limit line and that section is to be removed.
3. All cleared storm debris including wood chips shall be removed and disposed of off site and is the sole responsibility of the contractor.
4. Sweeping shall be done before moving onto the next area and as required to remove any loose material. Contractor shall clear roadways, driveways, ditches and gutters of cleared material.
5. Contractor may choose to work on any road group in any order. It is not required to work on the roads in the order they are listed.
6. The contractor shall notify the Public Works Inspector of any large items of trash or other discarded items that are encountered within the storm debris areas. It shall not be the Contractor's responsibility to dispose of any single item in excess of 20 pounds in weight.

Additional Notes:

1. Submit an updated traffic plan that includes specific rolling traffic plan for storm debris removal.