


**CURB RAMP DETAIL**

- NOTES:**
- COUNTER SLOPES OF ADJOINING GUTTERS AND ROAD SURFACES IMMEDIATELY ADJACENT TO AND WITHIN 24-INCHES OF THE CURB RAMP SHALL NOT BE STEEPER THAN 1V:20H (5.0%).
  - CURB RAMPS SHALL HAVE A DETECTABLE WARNING SURFACE THAT EXTENDS THE FULL WIDTH AND 3'-0" DEPTH OF THE RAMP. WARNING SURFACES SHALL CONFORM TO THE REQUIREMENTS OF CALTRANS STANDARD SPECIFICATIONS.
  - SIDEWALK AND RAMP THICKNESS, "T", SHALL BE 4" MINIMUM.

**LEGEND**

	EXISTING CURB
	PROPOSED 6" CURB
	PROPOSED PAINTED RED CURB, 'NO PARKING' STRIPING
	EXISTING CONCRETE TO BE REMOVED
	PROPOSED 4" PERVIOUS CONCRETE TO MATCH EXISTING SIDEWALK
	EXISTING CONCRETE



**NELSON ENGINEERING**  
Civil Engineering, Surveying & Land Planning  
14028 Carnas Court  
Penn Valley, CA 95946  
(530) 432-4818  
www.nelsonengineer.com

EXHIBIT FOR:  
**NEVADA COUNTY - CROSSWALK**  
950 MAIDU AVE, NEVADA CITY, CA 95959  
A.P.N. 05-020-22