

EXHIBIT A SCOPE OF WORK

Item 1: Remove remaining storm debris from the February/March 2023 Winter Storm along approximately 70 miles of County maintained roadways as listed in Exhibit B. Removal of this material will include the following:

1. Removal of all storm debris including fallen trees of all sizes, broken limbs, and small branches larger than 1 inch in diameter and 1 foot in length, and litter under 20 pounds (only in areas with storm debris damage) on both sides of the road that rests within 15 feet from the road edge.
2. Any downed trees that extend past 15 feet from the road edge shall be cut at the limit line and that section is to be removed.
3. All cleared storm debris including wood chips shall be removed and disposed of offsite and is the sole responsibility of the contractor.
4. Sweeping shall be done before moving onto the next area and as required to remove any loose material. Contractor shall clear roadways, driveways, ditches and gutters of cleared material.
5. Contractor may choose to work on any road group in any order. It is not required to work on the roads in the order they are listed.
6. The contractor shall notify the Public Works Inspector of any large items of trash or other discarded items that are encountered within the storm debris areas. It shall not be the Contractor's responsibility to dispose of any single item in excess of 20 pounds in weight.

Additional Notes:

1. Submit an updated traffic plan that includes specific rolling traffic plan for storm debris removal.
2. See additional Force Account worksheets, changes to sheets are at the discretion of Director of Public works
3. Exact quantities of debris removed to be determined in the field and paid per load according to the rate sheet.