

April 5, 2022

Chad McBride  
Wastewater Plant Operations Supervisor  
950 Maidu Ave.  
Nevada City, CA 95959

Dear Mr. McBride:

Synagro WWT, Inc. CA class A general engineering contractor, license #801688, DIR registration #100006919, is pleased to provide the following sub-quote to dry and remove sludge from the Nevada County Sanitation District – Penn Valley effluent reservoir per project specifications provided. Synagro's scope of work includes the following:

- Mobilization of equipment and personnel
- Drying of biosolids in place.
- Transfer of dried biosolids and vegetation from effluent reservoir to staging area accessible to trucks
- Loading, transport and lawful disposal of biosolids – estimated 100 dry tons
- Demobilization of equipment and personnel.

Synagro anticipates up to 4 weeks for sludge drying, loading, transportation and disposal of sludge. This includes the time required to remove and relocate the vegetation and rip-rap.

Other terms and conditions:

- The work is to be performed during dry weather months, April 15 to September 30.
- Sludge removal will be limited to sludge as specified and specifically excludes the removal and disposal of sludge contaminated pond bottom.
- Synagro will perform CA Title 22 testing to obtain a lawful landfill disposal profile. The project owner or authorized representative shall sign the profile as generator of the material.
- The effluent reservoir will be cleaned sufficiently to facilitate examination of the pond bottom by others for sludge contamination.
- Synagro and any on site subcontractors will pay not less than the general prevailing rate of wages for the job classifications employed on the project.
- Bonding rate of 1.5%, if required.
- The dry ton pricing included herein is based on the actual wet tons disposed as determined by landfill scale tickets multiplied by the percent solids as determined by a California State certified laboratory. It is anticipated that the percent solids will be 40% or more. A sample calculation is as follows:

Total tonnage per landfill scale tickets	210 tons
Average percent solids	47.5%
Total dry tons (210 x .475) =	99.75 Dry tons

Synagro's pricing for the above scope of services is as follows:

Description	Unit of Measure	Units	Unit Price	Extended
Mobilization and Demobilization	Lump Sum	1	\$19,850.00	\$ 19,850.00
CA Title 22 Testing	Lump Sum	1	\$ 1,450.00	\$ 1,450.00
Drying and stacking of sludge and vegetation	Lump Sum	1	\$97,757.00	\$ 97,757.00
Transfer of sludge and vegetation from pond to loading/staging area	Lump Sum	1	\$29,550.00	\$ 29,550.00
Loading, transportation and lawful disposal of dried sludge	Dry ton	100 (estimated quantity)	\$ 258.00	\$ 25,800.00
<b>Total</b>				<b>\$174,407.00</b>

This proposal is subject to execution of a mutually acceptable agreement between Synagro and the District and is subject to Synagro's standard terms and conditions, which are attached.

If you have any questions or require further information, please call me at 650-333-0729.

Very truly yours,

*John Pugliaresi*

John Pugliaresi  
Synagro WWT Inc.